



Important:

- All lintel bars must be propped until mortar is set (7 days).
- It is important to allow the first 3 courses of the brickwork over an opening to set before laying any more bricks above.
- Provide brick ties within the bottom two courses.

Note

- For openings greater than 2.0m, provide a landing for the lintel of 200mm for each side of the opening.
For openings less than 2.0m allow 100mm each side of opening.
- Mortar joints 10mm \pm 3, 6mm max rake (Hard-tooled concave joint preferred).

© 2019 Petros Holdings Ltd

Mineral Plaster
Technology

61 Hillside Rd, Wairau Valley
Auckland 0627
New Zealand
www.mineralplaster.co.nz Ph: 0800 25 23 678

MPT Stoneclad System

Window Head - Aluminium

Reference: MPT_S027

Date: September 2019

Scale: 1 : 4 @ A4

Revision: 2