

Important:

- a. All lintel bars must be propped until mortar is set (7 days).
- b. It is important to allow the first 3 courses of the brickwork over an opening to set before laying any more bricks above.
- c. Provide brick ties within the bottom two courses.

Note

- For openings greater than 2.0m, provide a landing for the lintel of 200mm for each side of the opening.
 - For openings less than 2.0m allow 100mm each side of opening.
- Mortar joints 10mm ± 3, 6mm max rake (Hard-tooled concave joint preferred).

© 2019 Petros Holdings Ltd



MPT Stoneclad System Window Head - Aluminium

	Reference: MPT_S027
	Date: September 2019
	Scale: 1:4 @ A4
	Revision: 2